Sl. No.	Descriptions	Unit
1	Outdoor PLZ IP Cameras with 20 X optical zoom with controller along with suitable mounting system (PTZ Pan Tilt and Zoom feature is availbale in this camera can be contolled by the software for pan Tilt and zoom feature at the contol center and can be programmed to view at different angles and zoom level continuosly. It operates at day and night and the viewing distance at clarity is about 100 metres	Nos
2	Bracket (Corner Mount / Pole Mount/ Wall Mount) for mounting the PTZ camera.	Nos
3	Outdoor 50 Meter IP Cameras with IR & Mounting Bracket (with IR for day and night vision and can provide a viewing distance of 50 metres)	Nos
4	Bracket and weatherproof Installation kit for 50 Meter IP Camera	Nos
5	Outdoor 30 Meter IP Cameras with IR & Mounting Bracket (with IR for day and night vision and can provide a viewing distance of 30 metres)	Nos
6	Bracket and weatherproof Installation kit for 30 Meter IP Camera	Nos
7	32 Channel NVR DS 7732 NI- E4 (with 4 Sata Option) the control box and the recording device to connect upto 32 devices, can be cascaded to provide additional cameras	Nos
8	12 TB NAS Box for Back up (NET GEAR) provides storage for the recorded data for quick view back and storage	Nos
9	4 TB SATA for storage and fitted in the NVR Device for storage	Nos
10	A suitable sheet metal control panel to house site Equipments (Weather Proof) The power supply and the ethernet connectivity adaptor is stored in this box.	Nos
11	Power supply for the camera.	Nos
12	Ethernet Switch for connectivity to Internet and Camera	Nos
13	Supply & Laying of Network and Power Cables from Camera to the control Box.	Nos
14	Video Manager Application Software for Display and Management of Camera on Video Display.	Nos
15	Installation, Erection & commissioning charges	Nos
	Grand Total	
	Add 10% KRIDL Charges	
	Add 1% Labour Cess	
	Net Total	

CERTIFICATE

1. Certified that the above work done satisfactory and no materials issued from departmentally.